



ASHWORTH

Case Study – Cross Rail Tunnel Central London (C610)

ASHWORTH

Specialist distributor of commercial
heating, plumbing & drainage
solutions

ASHWORTH

Coppergate House,
10 White's Row,
London
E1 7NF



- Project Value - £2.6m with goods supplied to ATC Canary Wharf
- Supply of Fire Protection feed lines for Hydrants.
- Supply also included bespoke Hydrant Tees and Anchor Brackets.

Project Timeline

Tender Stage – November 2014 to November 2015

Contract Award – December 2015

Project Delayed – March 2016 to August 2016

Final Deliveries – October 2018

Manufacturing UK

Steel Pipes – Tata

Welding Operations – Oldham and Essex

Ashworth Solutions

Reduced cost and unit weight per pipe by offering a thinner wall pipe going from 6.4mm to 5.6mm wall, whilst still retaining a 90-bar rated pipe

Bespoke Hydrant Tees and Anchor Brackets which reduced cost against the standard manufacturer's fittings.

Supplied a fabrication service for spool pieces in Galvanised carbon and stainless steel based from drawings.

Storage

The pipe was stored in Rochester and given a bespoke allocated area.

The material was stock checked every 3 months.

Delivery

Pipes were loaded to the customers weekly call off programme and dispatched on a daily delivery service.

Every delivery was given a unique despatch number and all material was traceable through heat numbers marked on the paperwork and items.

Supplied to two individual receiving sites in London

Delivery

Ashworth Fleet made all 140 individual deliveries.



ASHWORTH
PEOPLE PRODUCTS SERVICE